

## **FRESNO COUNTY FIRE PROTECTION DISTRICT**

### **ADDENDUM NO. 1**

**DATE:** February 26, 2024

**BID:** FIRE STATION 94 ASPHALT PROJECT

**DUE DATE:** MARCH 7<sup>TH</sup> BY 3:00 P.M. PDT

**TO:** ALL BID DOCUMENT HOLDERS

This addendum clarifies the original scope of work as noted below. This addendum consists of one page

### **Scope of Work**

The Fresno County Fire Protection District (District) is seeking bids for qualified contractors to provide Asphalt Replacement at Fire Station 94, located at 2412 W. Dorris Ave Coalinga CA, 93210-9752. The District request bids from individuals and companies whose combination of experience and expertise will provide timely, cost-effective and quality professional service.

Contractor will perform the following:

- Traffic Control
- Job Site Management
- Prepare and Implement Water Pollution Control Program (WPCP)
- Removal and disposal of existing asphalt
- Grading and drainage as needed, replace asphalt hot mix asphalt (Type A ¾" grading) PG 64-10 must meet performance criteria at an average 7-day maximum pavement temperature of 64°C and also at a minimum pavement temperature of -10°C
- Tack coat, Parking lot striping, Finishing Roadway
- Return work site to finished condition once installation is completed

**Edit, Page 3, Scope of Work**

**Full Depth Milling and Replacement of Asphalt**

### **Summary of Questions and Clarifications**

***Q1. What is the estimated square footage of the area.***

**A1.** Estimated square footage 17,811