

FRESNO COUNTY FIRE PROTECTION DISTRICT

ADDENDUM NO. 1

DATE: October 17, 2024

BID: FIRE STATION 87 ASPHALT PROJECT

DUE DATE: THURSDAY OCTOBER 31ST BY 3:00 P.M. PST

TO: ALL BID DOCUMENT HOLDERS

This addendum clarifies the original scope of work as noted below. This addendum consists of one page

Scope of Work

The Fresno County Fire Protection District (District) is seeking bids for qualified contractors to provide Asphalt Replacement at Fire Station 87, located at 4706 E Drummond Ave Fresno CA 93725. The District request bids from individuals and companies whose combination of experience and expertise will provide timely, cost-effective and quality professional service.

Contractor will perform the following:

- Traffic Control
- Job Site Management
- Engineering and Permits For Project (Certified Grading Plans)
- Prepare and Implement Water Pollution Control Program (WPCP)
- Removal and disposal of existing asphalt, (Full depth milling and replacement of asphalt)
- Grading and drainage as needed, replace asphalt hot mix asphalt (Type A ¾" grading) PG 64-10 must meet performance criteria at an average 7-day maximum pavement temperature of 64°C and also at a minimum pavement temperature of -10°C, estimated square footage 17,811
- Tack coat, Parking lot striping, Finishing Roadway
- Return work site to finished condition once installation is completed

Edit, Page 3, Scope of Work

3 Inch Asphalt, 6 Inch Base= 3/6
21 Parking Stalls for Striping
Concrete Gutter approximately 36 Feet
Entry/Exit for Apparatus (Fire Engine)