

FRESNO COUNTY FIRE PROTECTION DISTRICT

ADDENDUM NO. 2

DATE: February 29, 2024

BID: FIRE STATION 87 ASPHALT PROJECT

DUE DATE: MARCH 7TH BY 3:00 P.M. PDT

TO: ALL BID DOCUMENT HOLDERS

This addendum clarifies the original scope of work as noted below. This addendum consists of two pages

Scope of Work

The District is seeking a professional General Engineering firm (Contractor) to complete the asphalt replacement at the Fresno County Fire Station 87, located at 4706. E Drummond Ave, Fresno CA, 93725-1602.

Contractor will perform the following:

- Traffic Control
- Job Site Management
- Prepare and Implement Water Pollution Control Program (WPCP)
- Removal and disposal of existing asphalt
- Grading and drainage as needed, replace asphalt hot mix asphalt (Type A ¾" grading) PG 64-10 must meet performance criteria at an average 7-day maximum pavement temperature of 64°C and also at a minimum pavement temperature of -10°C
- Tack coat, Parking lot striping, Finishing Roadway
- Return work site to finished condition once installation is completed

Edit, Page 3, Scope of Work

Full Depth Milling and Replacement of Asphalt

Summary of Questions and Clarifications

Q1. What is the estimated square footage of the area.

A1. Estimated square footage 17,811

Q2. Is there construction water available at both sites ? Will there be a cost for the water?

A2. Both sites have water fill on site without charge.

Q3. Should we add cost for encroachment permits with Cal Trans and City of Fresno or will the district apply for the permits?

A3. Contractor is responsible for all permits
